

Collins Architectural Group, p.s.
950 12th Avenue, Suite 200
Longview, WA 98632

Addendum No. 2

Page No. 1 of 3

Date: May 18th, 2022

**Project: Longview Public Schools
Mark Morris High School Locker Rooms Remodel
Longview, WA**

Notice to Contractor:

The following changes in the Contract Documents, including the Drawings and Specifications, constitute this Addendum. All changes included in Addenda shall become a part of the Contract Documents for this Project. Any changes herein offset only the specific Drawings or Notes on Drawings or words or paragraphs in Specifications referenced to and the balance of the Drawings shall remain in full force.

ARCHITECTURAL SPECIFICATION

| <u>ITEM</u> | <u>SHEET NO./ SECTION NO.</u> | <u>DESCRIPTION</u> |
|-------------|-----------------------------------|---|
| 1.0 | Walk-Thru Attd | See the walk-through attendance sheet attached on page 3. |
| 1.1 | A3.1, note 20 | No new water closet required. Only a new flush valve is required. |
| 1.2 | A3.2 | In the girl's locker room, the locker bench legs shall remain in place. The owner will paint them. |
| 1.3 | A3.2 | In the girl's locker room, all existing HVAC ceiling returns/supplies shall be relocated into the new ceiling grid. Provide new grills to fit in the new ceiling grid and any necessary duct work for extensions into the new grid. |
| 1.4 | A3.2 | In the girl's locker room, there is no work associated with the drinking fountain other than masking it off to paint. |

WALK-THROUGH QUESTIONS:

Who is responsible for paying the permit?

The owner is responsible for the payment of the general building permit.

Who is the main point of contact for this project?

Jared Bradshaw-Vinson with Collins will be the main point of contact. Jason Reetz shall be cc'd in email correspondence.

Does the contract start date begin after the contract has been signed around or procurement of material in hand?

Contract start date shall be when the contract is signed to begin ordering the necessary materials, equipment, etc. Per the contract documents, onsite work can start June 20th, 2022.

Product Approvals:

Specified Product

Metal Lockers

Approved Product

ASI Storage Lockers

Fluid Applied Flooring

Master Builders:

MasterTop 1234 (Shower and toilet area only)

MasterTop 1851SRS CF (w/ Glass Beads)

(Other areas noted to receive fluid applied Flooring)

(This product may involve more preparation work than the BOD Semco Flooring)

Pre-Bid Walkthrough – 5/12/2022 @ 3:30 PM

MARK MORRIS LOCKER ROOMS REMODEL Walkthrough Attendance

| NAME | CONTACT |
|------------------------------|-------------------------|
| Jessica Reeves – JH Kelly | JHKellybids@JHKelly.com |
| John Jones – Busack Electric | 360-414-0144 |
| Jose Valencia – JH Kelly | jvalencia@jhkelly.com |

Pre-Bid Walkthrough – 5/13/2022 @ 3:30 PM

MARK MORRIS LOCKER ROOMS REMODEL Walkthrough Attendance

| NAME | CONTACT |
|---|---|
| Kurt Moyer – Pacific Tech Const. | Slate Miller: 360-414-8084 estimating@pactechgroup.com |
| Dan Walker – First Cascade Construction | Nick Conway: 503-713-3097 nickc@firstcascade.com |